कार्यालय, प्रधानाचार्य एवं मुख्य कार्यपालन अधिकारी
हकीम सैयद ज़ियाउल हसन,शासकीय(स्वशासी)यूनानी चिकित्सा महाविद्यालय
(कोलार–नेहरू नगर बायपास रोड, मेनिट के पीछे,भोपाल 462003)
Web: www.gumcbhopal.in E.mail: gumcbhopal@gmail.com दूरभाष क्रं. –0755–2970354

(स्थानीय महाविद्यालय से सम्बद्ध चिकित्सालय में फायर मैनेजमेन्ट सिस्टम विकसित किये जाने हेतु द्वितीय ई–निविदा के नियम एवं शर्ते)

हकीम सैयद ज़ियाउल हसन शासकीय (स्वशासी) यूनानी चिकित्सा महाविद्यालय से सम्बद्ध चिकित्सालय में फायर मैनेजमेन्ट सिस्टम विकसित करने हेतु (वर्ष 2026–27) ई–निविदा प्रकिया के अंतर्गत निविदाए आमंत्रित की जाती है, जो कि https://mptenders.gov.in पर निर्धारित समयावधि में उपलब्ध है। निविदा प्रस्तुत करने के नियम निर्देश एवं शर्ते महाविद्यालय की वेबसाइट www.gumcbhopal.in पर भी प्रदर्शित हैं।

1. ई–निविदा जमा करने की अंतिम तिथि 24.03.2026 को सायं 05.00 बजे तक है। ई–तकनीकी निविदा खोले जाने की दिनांक 26.03.2026 दोपहर 02.00 बजे है।
2. ई–निविदा बिड़ दस्तावेज हस्तांतरणीय नहीं हैं।
3. इच्छुक ई–निविदाकर्ता ऑनलाइन mptenders.gov.in से ई–निविदा राशि रू. 1000/– का भुगतान कर सकते हैं, जिसको mptenders.gov.in पर तकनीकी एवं वित्तीय निविदा पृथक–पृथक ऑनलाईन सबमिट की जाना है।
4. ई.एम.डी.राशि रूपये 50000.00 शब्दों में (पचास हजार मात्र) जिसे ई–पेमेन्ट के माध्यम से mptenders.gov.in पर tender सबमिट करते समय पेमेन्ट करना होगा। ई.एम.डी. राशि सफल निविदाकार को अनुबंध होने पर नियमानुसार वापस की जावेगी, शेष निविदाकारों की ई.एम.डी.राशि mptenders.gov.in के माध्यम से लौटा दी जावेगी। सफल निविदाकार को निष्पादन प्रतिभूति राशि 100000.00 रूपये (02 प्रतिशत) बैंक ड्राफ्ट के माध्यम से महाविद्यालय में जमा करना होगी। निष्पादन प्रतिपूर्ति राशि बिना ब्याज के अनुबंध समाप्त होने पर वापस लौटा दी जावेगी।
5. अनुबंधित फर्म को प्रपत्र–02 में उल्लेखित सीट अनुसार अग्नि शमन सामग्री की आपूर्ति अनिवार्य है। इस हेतु कोई भाड़ा/हम्माली पृथक से देय नहीं होगी।
6. वित्तीय निविदा प्रपत्र–03 अनुसार दरें https://mptenders.gov.in पर ई–निविदा की एक्सल शीट BOQ में ही अंकित करना है। निविदा मूल्यों में सकल योग (Aggregate) को विचार में लिया जा सकेगा।
7. किसी भी प्रकार की शिकायत प्राप्त होने पर तथा नियम शर्तों का पालन न करने पर अथवा सन्तोषजनक सेवा न पाये जाने पर अनुबंध तत्काल निरस्त कर दिये जावेगें एवं सम्पूर्ण जिम्मेदारी संबंधित फर्म की होगी। ऐसी स्थिति में जमा निष्पादन प्रतिभूति की राशि राजसात कर ली जावेगी, तथा संबंधित फर्म पर ब्लैक लिस्टिंग की कार्यवाही की

21/2/26 21/2/26

Scanned with CamScanner

जावेगी, एवं उपरोक्त अग्नि शमन कार्य की आपूर्ति हेतु एल–02 फर्म से एल--01 की दरों पर अनुबंध किया जायेगा।

8. सफल निविदाकार से किया गया अनुबंध 31 मार्च 2027 तक की अवधि तक के लिये मान्य होगा।
9. ई–निविदा स्वीकार होने पर सफल निविदाकार को एक अनुबंध राशि रूपये 100.00 के नॉन ज्यूडिशियल स्टाम्प पेपर पर नोटरी कर प्रस्तुत करना अनिवार्य है। जिसका व्यय निविदाकार को वहन करना होगा।
10. निविदाकर्ता फर्म भोपाल नगर निगम सीमा में स्थापित होना चाहिये जिसका गुमास्ता तकनीकी निविदा के अभिलेखों के साथ संलग्न करना आवश्यक होगा।
11. निविदाकर्ता के पास स्वयं अथवा फर्म का पैन नंबर होना चाहिये जिसकी प्रतिलिपि तकनीकी निविदा के अभिलेखों के साथ संलग्न करना आवश्यक होगा।
12. निविदाकर्ता के पास जी.एस.टी. नम्बर होना आवश्यक है जिसकी प्रतिलिपि तकनीकी निविदा के अभिलेखों के साथ संलग्न करना आवश्यक होगा।
13. निविदाकार के पास प्रपत्र– 02 अनुसार फायर कार्य संबंधी दस्तावेज होना चाहिए।
14. निविदाकार के पास शासकीय भवनों में फायर मैनेजमेन्ट सिस्टम विकसित करने का अनुभव होना चाहिए।
15. निविदाकर्ता फर्म का वित्तीय वर्ष 2023–24 अथवा 2024–25 का टर्न ओवर न्यूनतम 25 लाख होना आवश्यक है, जिसके साक्ष्य के रूप में वित्तीय वर्ष 2023–24 अथवा 2024–25 की आयकर विवरणी की प्रति, बैलेंस शीट, लाभ–हानि पत्रक (चाटेर्ड एकाउन्टेन्ट द्वारा प्रमाणित) एवं वित्तीय वर्ष 2023–24/2024–25 की आयकर विवरणी तकनीकी निविदा के दस्तावेजों के साथ अपलोड करना आवश्यक है।
16. निविदाकर्ता द्वारा कार्यादेश का कुछ भाग या पूर्ण भाग अन्य किसी ठेकेदार/व्यक्ति को नहीं सौंपेगा यदि किसी निविदाकर्ता द्वारा किसी अन्य फर्म/व्यक्ति को कार्य सौंपा जाता है, या कार्य कराता पाया जाता है तो उसका अनुबंध समाप्त कर फर्म को Black listed किया जायेगा।
17. आवेदनकर्ता फर्म प्रदेश के किसी भी शासकीय संस्था से ब्लैक लिस्टेड नहीं होनी चाहिए। यदि जानकारी प्राप्त होती है, तो निष्पादन प्रतिभूति राशि राजसात कर संबंधित फर्म की निविदा/अनुबंध निरस्त कर दिया जावेगा। ब्लैक लिस्टेड न होने का घोषणा/शपथ पत्र राशि रू. 100.00 सौ मात्र के नॉन ज्युडीशियल स्टांप पर नोटराइज कराकर तकनीकी निविदा के साथ संलग्न करना अनिवार्य होगा।
18. ई–निविदा खोलते समय निविदाकर्ता अथवा उनके प्रतिनिधि (अधिकृत पत्र प्रस्तुत करने पर) शामिल हो सकते हैं।
19. ई–निविदा को स्वीकृत अथवा अस्वीकृत करने का सम्पूर्ण अधिकार प्रधानाचार्य को होगा, जो सभी को मान्य एवं बंधनकारी होगा।
20. किसी भी विवाद की स्थिति में प्रधानाचार्य का निर्णय अंतिम एवं सर्वमान्य होगा, इसका पालन करना होगा।

21/2/26

21/2/26

Scanned with CamScanner

अन्य कोई शर्त आवश्यकता पड़ने पर मान्य करना होगी।

22. ई–तकनीकी निविदा का विश्लेषण करते समय प्रपत्र 02 , 03 , 04 एवं 05 अनुसार समस्त वांछित अभिलेख ऑनलाईन अपलोड करना अनिवार्य है, अन्यथा कि स्थिति में तकनीकी निविदा अमान्य किये जायेंगें।

23. किसी भी विवाद की स्थिति में न्याय क्षेत्र भोपाल रहेगा।

प्रधानाचार्य एवं मुख्य कार्यपालन अधिकारी
हकीम सैयद ज़ियाउल हसन
शासकीय(स्वशासी) यूनानी चिकित्सा
महाविद्यालय, भोपाल।

21/2/26

21/2/26

Scanned with CamScanner

हकीम सैयद जियाउल हसन,शासकीय(स्वशासी) यूनानी चिकित्सा महाविद्यालय भोपाल

(महाविद्यालयसे सम्बद्ध चिकित्सालय में फायर मैनेजमेन्ट सिस्टम लगाये जाने हेतु निविदा का प्रारूप)

(ई–वित्तीय निविदा का प्रपत्र–02)

S. No	Description	Qty	Unit	Rate
1	**Diesel engine driven fire fighting pump water cooled** Supplying, installation, testing & commissioning of Stand by -Engine Engine 36HP Pump Driven pump set capable of delivered 1620 LPM @ 60 mtr to maintain 3.5 kg/cm2 pressure at highest and farthest outlet with NFPA-20 compliance (150%flow) and approved with local authority Horizontal end suction long coupled with special CI CED coating casing bronze impeller ss shaft with mechanical seal with radiator cooled engine having 2920 RPM 12v auto / manual starting arrangement base frame coupling and coupling guard , fuel tank for engine to sustain at 6/8 hours in case of emergency, Suitable auto charging system to charge the engine battery with lugs and cables, suitable inbuilt Auto controller for engine to operate. Pump set should be factory fitted and factory tested, Local assembled products not approved from any OEM or contracts ,Pump NPSH should be least minimum ,On site Service would be preferable, **Make:- Kirloskar/Lubi/Grundfos**	1	Nos	
2	**Horizontally mounted coupled motor (Eff-1)** Supplying, installation, testing & commissioning of **Main pump electric** driven Pump capable of delivering 1620 LPM @ 60 mtr 30HP to maintain 3.5 kg /cm2 pressure at highest and farthest outlet with NFPA-20 compliance (150% flow) and approved with local authority. Horizontal end suction long coupled with special CI CED coating casing bronze impeller ss shaft with mechanical seal with TEFC 2900 rpm 3 phase IE2 motor base frame coupling and coupling guard. Pump set should be factory fitted and factory tested, Local assembled products not approved from any OEM or contracts .Pump NPSH should be least minimum On site Service would be preferable. **Make:- Kirloskar/Lubi/Grundfos**	1	Nos	

21/2/26 21/2/26

Scanned with CamScanner

	Jockey pump horizontally mounted coupled motor: Supplying, installation, testing & commissioning of **Jockey pump** electric driven Pump capable of delivered 180 LPM @ 60 mtr to maintain 6 kg/cm2 pressure at line with NFPA-20 compliance and approved with local authority Horizontal end suction long coupled with special CI CED coating casing bronze impeller ss shaft with mechanical seal with TEFC 2900 rpm 3 phase IE2 motor base frame coupling and coupling guard. Pump set should be factory fitted and factory tested, Local assembled products not approved from any OEM or contracts ,Pump NPSH should be least minimum On-site Service would be preferable. **Make:- Kirloskar/Lubi/Grundfos**	1	No Nos s	
4	**Fire pumps electrical panel: Fire pumps electrical panel,** Cubical type floor mounted electrical control panel Supplying, installation, testing & commissioning of cubical type floor mounted electrical control panel of 2.0 mm thick CRCA sheet suitable for 380-415 Volt, 50 Hz, 3 Ph supply, NEMA type 2 (IP 31) drip proof metal free standing enclosure for fire fighting pumps with suitable star-delta starter including indicating lamps, ammeter, voltmeter, selector switches for each, incoming and outgoing feeder, auxiliary switches, dry suction cut off, single phase preventer, alu. bus bar etc. The panel shall be provided with interlocking arrangement between electric motor driven and diesel engine driven pumps so that only one pump can operate at one time and in case of any failure in electric motor driven pump the diesel engine driven pump shall operate automatically. The installation shall include all control wring, accommodation for battery charger etc. and connections as required. Incoming : 1.No. 250 Amp 4 Pole MCCB, 35 KA 1 Set 300 Amp, 500V, capacity pressure switch to panel, pump ON indicating lamp. e.c. complete as required. Make:- Agni/Lubi/L&T/	1	Set	
5	**DOL Starter** Supply installation, testing and commissioning of approved make DOL	3	Nos	

21/2/26 21/2/26

Scanned with CamScanner

	starter 7.5/10 hp, 3 phase, 50 Hz, 415V, i/c single phase preventer, incoming MCB 32A 4P, 10KA, in outdoor type enclosure, connections, as required as per specifications.			
6	**2 Loop microprocessor addressable fire alarm panel** Supply, installation, testing and commissioning of **2 loop microprocessor based intelligent and electronically addressable**, modular, each loop capacity of 254 detectors and device. Fire alarm control panel with 7 inch touch screen LCD display, multiple access levels, 10,000 event history logs in the non volatile memory (EEPROM). Network upto 512 Nodes and support at least 8 Repeaters, Built-in Printer. The panel should be modular microprocessor based in nature. The panel shall have 240V AC power supply. The panel shall be EN 54/UL certification. **Make- Honeywell Morley / Bosch / Fyrlaast by Agni / Agni**	1	Nos	
7	**Active and networkable repeater panel** Supply, installation, testing and commissioning of active and networkable repeater panel with LCD control panel with 7 inch touch screen LCD display, display complete system function keys for programming and control like system reset, alarm acknowledgement, alarm silence, trouble acknowledgement UL/EN54 certified. **Make- Honeywell Morley / Bosch / Fyrlaast by Agni / Agni**	2	Nos	
8	**Addressable– automatic LED smoke detector** Supply, installation, testing and commissioning of addressable– automatic **LED smoke detector** with integrated light-scattering smoke sensors using LEDs, Inbuilt Isolator, automatic addressing shall be UL/EN54 certified **Make- Honeywell Morley / Bosch / Fyrlaast by Agni / Agni**	180	Nos	
9	**Indoor addressable manual break glass unit.** Supply, installation, testing and commissioning of indoor addressable manual break glass unit (double action) with inbuilt isolators, with flexible network structures & necessary fixing arrangements	18	Nos	

21/2/26 21/2/26

Scanned with CamScanner

	with key complete as required shall be UL/EN54 certified. **Make- Honeywell Morley / Bosch / Fyrlaast by Agni / Agni**			
10	**Fire Emergency Telephone System**: Supply, installation, testing and commissioning of Addressable Fire Telephone Control Panel – 1 Nos, Mobile Handset -- 2Nos. Fire Telephone Jack Socket – 5 Nos **Make- Honeywell Morley / Bosch / Fyrlaast by Agni / Agni**	1	Set	
11	**Fire Survival Cable** Supply of XLPE insulated 1.5 sq. mm. Armoured 2 core FRLSZH fire alarm cable (RED) Fire Survival Cable conforming IS-7098 (Part-1) 1988, 1100 Volt grade, 2/3/4/8/10/12 core ISI marked with copper stranded/solid conductor. **Make- Polycab/Fyrlaast by Agni / Agni/finolax**	2800	Rm	
12	**XLPE insulated power cable**, al. conductor Supply of XLPE insulated power cable (conforming IS-7098 Part-I) 1100 Volt grade, 1 core/2 core/3½ core/4 core ISI marked with alu. stranded /solid conductor. **10 sq. mm.**	200m	Rm	
13	**2 PAIR TELEPHONE CABLE** (0.5 mm diameter ,pure copper,good quality, pvc coated,fire retardent)	250m	Rm	
	'C' class heavy duty MS pipe in on wall/ceiling Providing laying, testing and commissioning of 'C' class heavy duty MS pipe confirming to IS 1239/3589 i/c fittings like elbows, tees, flanges, reducer, jointing with nuts bolts, gaskets and welding etc. and fixing the pipe on wall/ceiling with suitable hangers, clamps, supports, as required and painting with two or more coats of synthetic. **Make- Jindal/Apollo/Tata**			
14	200 mm dia	30m	Rm	
15	150 mm dia	300m	Rm	
16	100 mm dia	100m	Rm	
17	80 mm dia	400m	Rm	
18	50 mm dia	200m	Rm	
19	25 mm dia	1500m	Rm	
Civil	**'C' class heavy duty MS pipe in underground** Providing laying, testing and commissioning of 'C' class heavy duty MS pipe confirming to			

21/2/26 21/2/21

	IS 1239/3589 underground i/c fittings like elbows, tees, flanges, tapers, jointing with nuts bolts, gaskets and welding etc. underground including excavation, road cutting and backfilling and providing, at prescribed intervals and anticorrosive treatment with coal tar/ asphalts tape as IS 10221, with 4mm thick fiber reinforced tape and 12mm overlap and refilling the trench etc. **Make- Jindal/Apollo**			
20	150 mm dia	250m	Rm	
21	**Air vessel** Providing and fixing air vessel made of 200-250mm dia, 8mm thick MS sheet, 1200mm in height with air release valve on top and flanged connection to riser, drain arrangement with 25 mm dia with wheel valve, with required accessories, pressure gauge and painting with synthetic enamel paint of approved shade as required . **Butterfly valve** Providing, fixing, testing and commissioning of butterfly valve PN 1.6, duly ISI marked complete with Nuts, Bolts, washers, gaskets, confirming to IS 13095, of following sizes as required. **Make – Kartar/Zoloto/Sant**	1	Nos	
22	200 mm dia	1	Nos	
23	150mm dia	5	Nos	
24	100mm dia	2	Nos	
25	50mm dia	6	Nos	
26	Ball valve (brass) Supply, installation, testing and commissioning of ball valve (brass) high or low pressure with plastic floats inclusive of all necessary required material, labor for mentioned below size. 25.00 mm **Dual plate non return valve** Providing, installation, testing and commissioning of dual plate non-return valve of following sizes confirming to IS 5312 complete with rubber gasket, GI bolts, nuts, washers etc. **Make – Kartar/Zoloto/Sant**			
27	150mm NRV	1	Nos	
28	100mm NRV	1	Nos	
29	80mm NRV	1	Nos	

21/2/26   21/2/26

Scanned with CamScanner

	Cutting holes R.C.C. floors and roofs Cutting holes upto 15x15 cm in R.C.C. floors and roofs for passing drain pipe etc. and repairing the hole after insertion of drain pipe etc. with cement concrete 1:2:4(1 cement : 2 sand ; 4 graded stone aggregate 20 mm nominal size) including finishing.	80	Nos	
31	**Foot Valve 200mm**	1	Nos	
32	**Foot Valve 150mm**	1	Nos	
33	**RRL hose pipe** Supplying and fixing dia,15m long, 63 mm dia RRL hose pipe with following dia male and female couplings duly binded with GI wire, rivets etc. confirming to IS 636 (type-A) as required. **Make – Kartar/Zoloto/New Age**	12	Nos	
34	**First -Aid hose reel** Providing and fixing first -Aid hose reel with MS construction spray painted in post office red, confirming to IS 884 with up-to-date amendments, complete with the following as required.) (a) 30-36m long 20mm (nominal internal) dia water hose thermoplastic (textile reinforced) type -2 as per IS 12585 (b) 20mm (nominal internal) dia globe valve and nozzle. (c) Drum and brackets for fixing the equipment on wall. (d) Connections from riser with 40 mm dia stop valve and M.S. pipe **Make – Kartar/Zoloto/New Age**	6	Nos	
35	**Hose Box** Providing and fixing hose cabinet of size 700x600x300mm made of 16 gauge thick MS sheet with 4 mm thick float glass doors in front painted "FIRE" in red paint i/c necessary locking arrangement suitable to accommodate external hydrant with butterfly valve 2 nos. 15m Long hose pipe, 1 no branch pipe mounted on wall or raised brick platform& duly painted with post office red externally and white internally with synthetic enamel paint complete in all respects for external hydrant. **Make – Kartar/Zoloto/New Age**	6	Nos	
36	**2-way fire brigade connection** Providing and fixing 2-way fire brigade connection (FBC) of CI body with2 nos. male instantaneous inlet couplings complete with	1	Nos	

21/2/26 21/2/26

Scanned with CamScanner

	cap and chain as required. For 150mm dia MS pipe connection, confirming to IS 904 as required. **Make – Kartar/Zoloto/New Age**			
37	**Single headed hydrant valve** Providing and fixing single headed hydrant valve with instantaneous female couplings of required dia with cast iron wheel ISI marked conforming to IS 5290 (Type -A) with blank cap and chain, adopter as required complete. **Make – Kartar/Zoloto/New Age**	6	Nos	
38	**Short metal branch pipe with nozzle** Providing and fixing 63mm metal branch pipe with 20mm (nominal internal diameter) size metal nozzle conforming to IS 903, suitable for instantaneous connection, to interconnect hose pipe coupling as required. **Make – Kartar/Zoloto/New Age/Armor**	6	Nos	
39	**Quartzoid bulb type sprinklers** Providing, fixing testing and commissioning of 15mm size quartzoid bulb type sprinklers, set to operate at 68/79 degree Centigrade. Pendent type/upright type/side wall type with required accessories complete. **Make-Agni/Tyco**	250	Nos	
40	**Rosette plate for sprinkler** Providing and installation of adjustable Rosette plate for sprinkle	250	Nos	
41	**Pressure switch** Providing and fixing Pressure switch in the MS pipe Line including connection etc. as required. Capacity 4.5 kg **Make - Danfoss**	3	Nos	
42	**Pressure Gauge** Pressure gauges Supplying &installation of pressure gauges with 15 mm dia brass check nut & capable of showing pressure reading from 0. to 30 kg **Make – H-Guru**	5	Nos	
43	**ABC Power type fire extinguishers** Providing and fixing of ABC Power type fire extinguishers consisting of welded M.S. cylindrical body, squeeze lever discharge valve fitted with pressure indicating gauge internal discharge tube 30 cm long high pressure discharge hose, discharge nozzle, suspension bracket. Conforming to IS: 15683 finished externally with red enamel paint fixed to wall with brackets complete with internal charge. Capacity 6.0 kg	20	Nos	

21/2/26 21/2/26

Scanned with CamScanner

	Carbon-di-oxide type fire extinguishers Providing and fixing of carbon-dioxide type fire extinguishers consisting of welded M.S. cylindrical body, squeeze lever discharge valve fitted with pressure indicating gauge internal discharge tube 30 cm long high pressure discharge hose, discharge nozzle, suspension bracket conforming to IS : 15683 finished externally with red enamel paint and fixed to wall with brackets complete with internal charge. **Capacity 4.5 kg**	4	Nos	
45 Civil	Fire pump house of fabricated iron and steel fabrication shed 12×12 feet	1	Set/Nos	
46	INCLUDE FIRE NOC liasoning from competant govt local body, drawing of installed fire system, fire plan and layout.	1	Set/Nos	
47	**ABC Power type Automatic fire extinguishers** Providing and fixing of ABC Power type fire extinguishers consisting of welded M.S. cylindrical body, squeeze lever discharge valve fitted with pressure indicating gauge internal discharge tube 30 cm long high pressure discharge hose, discharge nozzle, suspension bracket. Conforming to IS: 15683 finished externally with red enamel paint fixed to wall with brackets complete with internal charge. Capacity 3.0 kg	1-10	Set/Nos	
48 Civil	Brick work, Plastering, Gate Installation & Demolition may required for a panel room	1	Nos	
49	After 1st year CMC Maintenance charge for the 2nd year	1	Nos	
			Total	

नोट – उक्त प्रपत्र प्रारूप मात्र है इस प्रपत्र के अनुसार दर राशि को ई–वित्तीय निविदा ऑनलाइन www.mptender.gov.in पर तकनीकी निविदा की एक्सल शीट BBQ में ही दर्ज करना है।

21/2/26 21/2/26

Scanned with CamScanner

हकीम सैयद ज़ियाउल हसन,शासकीय(स्वशासी) यूनानी चिकित्सा महाविद्यालय भोपाल

(महाविद्यालय से सम्बद्ध चिकित्सालय में फायर मैनेजमेन्ट सिस्टम लगाये जाने हेतु निविदा का प्रारूप)

(ई–वित्तीय निविदा का प्रपत्र–03)

S. No	Description	Qty	Unit	Rate without GST
1	**Selection of Agency for Supplying, installation, testing & Commissioning of Fire Fighting System in HSZH Govt Unani medical College Bhopal as per Annexure -02**	**1**	**Nos**	

नोट – उक्त प्रपत्र प्रारूप मात्र है इस प्रपत्र के अनुसार दर राशि को ई–वित्तीय निविदा ऑनलाइन www.mptender.gov.in पर तकनीकी निविदा की एक्सल शीट BBQ में ही दर्ज करना है।

21/2/26

21/2/26

Scanned with CamScanner

//शपथ –पत्र //

मैं ....पिता श्री........................ ....निवासी ....उम्र .... वर्ष शपथ पूर्वक कथन करता हूं कि स्थानीय महाविद्यालय से सम्बद्ध चिकित्सालय में फायर मैनेजमेन्ट सिस्टम विकसित करने हेतु निविदा में दी गई समस्त शर्तो का पूर्ण होशो–हवास में अध्ययन कर लिया है जिसकी समस्त शर्ते मुझे मान्य है। एवं मेरे द्वारा प्रस्तुत समस्त दस्तावेज़ वैधानिक हैं एवं किसी भी शासकीय संस्था द्वारा मेंरी फर्म को ब्लैक लिस्टेड नहीं किया गया है। निविदा की शर्तो का पालन नहीं करने एवं मेरे द्वारा प्रस्तुत दस्तावेज त्रुटिपूर्ण पाये जाने की स्थिति में यदि मेरी निविदा/अनुबंध निरस्त की जाती है, तो मुझे किसी प्रकार की आपत्ति नही होगी।

गवाह/साक्षी के हस्ताक्षर ....
गवाह/साक्षी का नाम ....
मोबाइल नं0 ....

निविदाकर्ता के हस्ताक्षर ....
निविदाकर्ता का नाम ....
मोबाइल नं0 ....

नोट :– उक्त शपथ पत्र राशि रु 100.00 एक सौ मात्र के नॉन ज्युडीशियल स्टांप पर नोटराइज कराकर तकनीकी निविदा के साथ संलग्न करना अनिवार्य होगा ।

21/2/26 21/2/26

Scanned with CamScanner

Additional Bidder Eligibility Criteria and Term & Conditions

1. Bidders are required to upload Approved En/UL Valid Certified datasheets along with the bid documents. Buyer can match and verify the data sheets with the product specifications offered.
2. The Bidder should be a manufacturer/Distributor/ Dealer /authorized agent and must have successfully supplied the same or in similar category (Fire and Telecom) in last three years from the date of publication of bid. Copies of relevant work-orders to be submitted along with the bid.
3. Bidders Must have ISO 9001 Certificate
4. Bidder should have Govt Authorised Fire consultant Empanelled Basic and copy of valid registration Certificate Must have to be uploaded.
5. The authorized bidder should possess a Bid Specific authorization (MAF) certificate (Fire Alarm & Fire Pump) directly from the OEM and the same should be submitted.
6. Bidder should not be blacklisted or barred by any Ministry of Government of India or any of the Government / PSUs or any other government department at the time of bidding. (Submit declaration duly sealed and signed by competent authority on 100 Rs Affidavit)
7. Bidder, if the bidder is an MSME registered MSME entity, should have MSME registration certificate from Competent Authority (Copy of Certificate to be attached) to get exemptions as per GOVT RULES
8. Bidders Average Turnover should be minimum 25 Lac in last three financial years, Documentary proofs to be attached.
9. Bidder must be MP-PWD registered contractor only, Attached certificate for same.
10. The contractor/Company should have local office in Bhopal.
11. Bidder Must be available for any Emergency.
12. Bidder must give 01 year CMC Maintenance for Fire Safety System.
13. The Final Payment of Bidder be made successfully after College Getting Fire NOC from Nagar Nigam Bhopal.
14. 3rd party inspection by competent person is mandatory, after inspection by competent person if there is any shortfall in work, it will have to be completed by L-1 bidder.

गवाह / साक्षी के हस्ताक्षर	निविदाकर्ता के हस्ताक्षर ....
गवाह / साक्षी का नाम	निविदाकर्ता का नाम ....
मोबाइल नं0	मोबाइल नं0 ....

21/2/26 21/2/26

Scanned with CamScanner

//चैक–लिस्ट//

उपरोक्त वर्णित नियम शर्तो अनुसार निम्न दस्तावेजो को तकनीकी निविदा प्रपत्र 05 अनुसार सबमिट करते समय आवश्यक रुप से संलग्न किया जाना है :–

क	दस्तावेज का नाम	संलग्न हॉ/नहीं
01	जीवित गुमास्ता संबधित कार्य का होना आवश्यक है जिसकी छाया प्रति	
02	पैन कार्ड की छाया प्रति	
03	जी.एस.टी.पंजीयन पत्र की प्रति (जी.एस.टी.जमा सम्बंधी विगत 02 वित्तीय वर्षो का ऑनलाईन पत्रक तकनीकी निविदा के दस्तावेजों के साथ संलग्न करना अनिवार्य है)	
04	निविदाकर्ता फर्म का वित्तीय वर्ष 2023–24 एवं 2024–25 का टर्न ओवर न्यूनतम 25 लाख होना आवश्यक है जिसके साक्ष्य के रुप में विगत तीन वित्तीय वर्षो की आयकर विवरणी	
05	ई.एम.डी.राशि का बैंक ड्राफ्ट (प्रधानाचार्य हकीम सैयद ज़ियाउल हसन शासकीय/स्वशासी यूनानी चिकित्सा महाविद्यालय भोपाल के नाम से)	
06	फायर मैनेजमेन्ट सिस्टम कार्य करने हेतु जीवित अप्रूव ई.एन./यू. एल. सर्टिफिकेट	
07	फायर मैनेजमेन्ट सिस्टम कार्य करने हेतु कम्पनी का अर्थॉराईजेशन सर्टिफिकेट	
08	आई.एस.ओ. 9001 सर्टिफिकेट	
09	निविदाकर्ता म.प्र. पी.डब्ल्यू.डी. रजिस्टर्ड कॉन्ट्रेक्टर होना अनिवार्य है, इस बावत् जारी सर्टिफिकेट	
10	शासकीय भवनों में फायर मैनेजमेन्ट सिस्टम विकसित करने संबंधी अनुभव प्रमाण पत्र	
11	कार्य पूर्ण होने पर महाविद्यालय द्वारा थर्ड पार्टी कंपेटेन्ट अथॉरिटी द्वारा इंस्पेक्शन/ऑडिट कराया जायेगा।	
12	निविदाकार फर्म किसी शासकीय/अशासकीय/अर्धशासकीय संस्था द्वारा ब्लैक लिस्ट नही होना चाहिऐ इस हेतु शपथ पत्र की प्रति	

निविदाकर्ता के हस्ताक्षर ....

निविदाकर्ता का नाम ....

मोबाइल नं0 ....

21/2/26 21/2/26

Scanned with CamScanner